



## MTA Press Releases

[Select Language](#) | ▼

Press Release

March 24, 2014

[Metro-North](#)

IMMEDIATE

### Metro-North Signal Upgrades Complete at Curves and Bridges

#### *Work Finished More Than Five Months Early*

MTA Metro-North Railroad has completed permanent changes to its signal system to ensure automatic speed enforcement at five critical curves and five moveable bridges in New York and Connecticut, more than five months ahead of schedule.

Today the railroad announced that with the completion of work at the Devon Bridge in Stratford, CT, last Thursday all the signal modifications ordered by the Federal Railroad Administration in December are now complete, well before the September 1, 2014 FRA deadline.

"The complete implementation of the requirements of the FRA's Emergency Order 29, issued on December 8, 2013, brings us another step closer to a safer railroad, which is our number one goal," said Metro-North President Joseph Giulietti, who started on February 10 of this year. "We will continue to take all necessary steps to restore Metro-North to greatness."

Signal engineers first designed modifications to the circuitry at each location by calculating where and when speed limits should be reduced. Then signal maintainers had to reconfigure wiring along the tracks that sends the signal to the train to control its speed. Extensive testing was then performed to confirm that the changes were working as designed.

The signal display observed by train engineers in their cabs now will automatically indicate reduced allowable speeds on the approaches to these 10 locations. If the engineer does not reduce the train's speed accordingly, the train will automatically come to a stop.

Metro-North Signal forces began work on changes to the Automatic Train Control system at Spuyten Duyvil just days after the fatal derailment and completed the modifications there on the same day the FRA order was issued.

Signal system modifications for the remaining four curves at Yonkers, White Plains, Bridgeport and Port Chester were all completed by February 8, ahead of the FRA March 1, target.

Work then shifted to the five moveable bridges on the New Haven Line at Cos Cob, South Norwalk, Westport, Bridgeport and Milford in Connecticut. The "Peck" Bridge in Bridgeport was completed first on January 18, 2014 and the fifth and final bridge at Devon was completed March 20, 2014.

The project was completed using Metro-North's own Signal Design and Construction forces.